

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co. Inc.

Complete Address Suite 800 200 W Douglas Wichita, Ks 67202

Lease Name Chitwood Unit Well No. J-4

Location NE/SW/NE Sec. 22 Twp. 28 Rge. 12 (E) (W) X

County Pratt Total Depth 4410

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks 67524 License No. 436

Operation Completed: Hour 12:00PM Day 7 Month 3 Year 1970

The above well was plugged as follows:

381 ft of 8 5/8 surface pipe circulated with 200 sacks cement.

4396 ft of 5 1/2 long string cemented with 200 sacks cement. Sand back

to 4375 ft, 5 sacks cement with bailer. Pulled 3000ft of 5 1/2. Mud to

250 ft, 10 ft rock briedge, 25 sacks cement. Mud to 40 ft, 10 ft

rock bridge, 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-9-70

INV. NO. 1560-w

Signed: A. Russell B. Chilton
Well Plugging Supervisor