

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Raymond Oil Co. Inc.

Complete Address Suite 800-200 W. Douglas Wichita, Ks 67202

Lease Name Chitwood Unit Well No. H-6

Location C/NE/NE/SE Sec. 22 Twp. 28 Rge. 12 (E) (W)X

County Pratt Total Depth 4491

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 2:00PM Day 17 Month 2 Year 1970

The above well was plugged as follows:

341 ft of 8 5/8 surface pipe circulated with 200 sacks cement. 4485 ft  
of 5 1/2 long string cemented with 250 sacks. p.B. at 4443 ft. Top perf.  
3751 ft. 3000 ft 5 1/2 pulled. Pushed plug to 3700 ft. 20 ft sand  
& 5 sacks cement. Mud to 250 ft, 10 ft rock bridge, 25 sacks cement.  
Mud to 40 ft, 10 ft rock bridge, 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 2/19/70  
INV. NO. 1459-W