

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-18920781-0000

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME NIPPLE

WELL NUMBER 1

SPOT LOCATION C-S/2-NW

SEC. 12 TWP 32 RGE. 35 (E) OR (W) (W)

COUNTY Stevens

LEASE OPERATOR BELCO ENERGY CORPORATION

ADDRESS 8908 S. Yale/Suite 340 Tulsa, Okla 74137-3522

PHONE # (918) 481-6020 OPERATORS LICENSE NO. 31269

~~DATE WELL COMPLETED~~ 1-17-85

PLUGGING COMMENCED 6-19-01

CHARACTER OF WELL oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 6-21-01

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

Is ACO-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? _____

~~PRODUCING FORMATION~~ CHESTER DEPTH TO TOP _____ BOTTOM T.D.

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION'S	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>CHESTER</u>	oil	5991	6012	8 5/8	1797	-0-
	oil	5520	5527	5 1/2	6450	-550-
				2 1/16	6000	-5305-
				2 1/16	5500	-5305-


DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Rods & tubing were removed & mud was placed in well-bore via pump & circulation method. CIBP was set @5290' w/2sx cement on top. 550' casing was pulled. Tubing ran to 1820'. Mix & pumped 40 sx. cement 1820' to 1520'. Mix & pump 40 sx. cement from 550' to 450'. Mix & pump 10 sx. cement 40' to surface Cut off 4' B.G.L. & welded steel ID plate on top.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR JERRY DUNKIN WELL SERVICES, INC. LICENSE No. 8733
ADDRESS P.O. Box 389 Enid, Oklahoma 73702

STATE OF _____ COUNTY OF _____, SS.

PAUL DAVIS (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.



(SIGNATURE) Paul Davis
(ADDRESS) 8908 S YALE TULSA OK 74137

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF AUGUST, 2001

Jerry Frohnappfel
NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-23-01

RECEIVED

AUG 20 2001

KCC WICHITA

FORM CP-4
REVISED 06-83

OK