

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20879 - 0000

LEASE NAME Katie Boles

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
660 Ft. North from SE corner

1320 Ft. West from SE corner

SEC. 26 TWP. 32S RGE. 35 (N) or KXX (W)

LEASE OPERATOR Mobil Oil Corporation

COUNTY Stevens

ADDRESS P. O. Box 5444 Denver, CO 80217

Date Well Completed 2-10-86

PHONE# (303) 298-2696 OPERATORS LICENSE NO. 5208

Plugging Commenced 4-4-86

Character of Well Plugged & Abandoned

Plugging Completed 4-5-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 6368

Show depth and thickness of all water, oil and gas formations.

8-5/8" @ 1768'
5-1/2" @ 6368'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set Baker CIBP @ 5880'. Dumped 2 sxs cement on plug. N/D BOP tbg. Head & adaptor flange.

Removed slips from csg via csp spear. Slacked off csg. Cut csg w/jet cut @ 2300'. Pumped

balanced plug of 40 sxs class H cmt @ 1815'. Laid down 35 its tbg. Set balanced plug of

25 sxs class H cmt @ 700'. Laid down 22 its tbg. Pumped 15 sxs class cmt for surface plug

from 0-30'. (If additional description is necessary, use BACK of this form.) Used drilling mud to displace cmt plugs.

Name of Plugging Contractor Halliburton License No. _____

Address Liberal, KS

STATE OF Colorado COUNTY OF Denver, ss.

J. E. Dawson (Employee of Operator) or Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. E. Dawson J. E. Dawson

Producing Accounting Supervisor

(Address) P. O. Box 5444 Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1986

Mary Ellen McFarland
Notary Public

My Commission Expires: 6/16/88