


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stevens County, Sec. 29 Twp. 32 Rge. 36W (E) (W)

Location as "NE/CNW/SW" or footage from lines C-2E-1/4

Lease Owner Walter Kuhn Drilling Co.

Lease Name Neuner Kuhn Well No. I

Office Address 726 Union Center Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 9-6 19 44

Application for plugging filed 8-30 19 64

Application for plugging approved 9-3 19 64

Plugging commenced 9-4 19 64

Plugging completed 9-9 19 64

Reason for abandonment of well or producing formation Replacement drilled

If a producing well is abandoned, date of last production July 19 64

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation Hugoton Depth to top 2630 Bottom 2755 Total Depth of Well 2755 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	640	none
				7"	2635	910'
				5 1/2" Liner	125	none
				5 1/2"	1830	1830'
						5 1/2 x 7" Packer

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand 2755 to 2630

Pump 20 sacks cement 2630 to 2542. Mud to 650 and 35 sacks cement 650 to 580. 15 sacks cement 30' to 0'. Out 10 3/4" casing off 3' below ground level and weld cap on same.

Completed 9-9-64.

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service

Address Box 506 Liberal, Kansas

STATE OF Kansas COUNTY OF Sedgewick, ss.

Owner & operator (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Kuhn
726 Union Center Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 64.

My commission expires May 16, 1967

Notary Public.

WELL LOG
Kuhn #1

29-32-36 W

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>RE MARKS</u>
Gyp & Sand	0	137	9-6-44
Sand, Clay & Gyp	137	503	
Gyp	630	640	Set 10 3/4" @ 640' w/ 100 Cmt. 9-7-44
Red Bed & Gyp	640	810	
Gyp, Red Bed & Sand	810	1312	
Red bed & Shells	1312	1740	
Shale & Shells	1740	1771	
Lime	1771	1794	
Shale And Anhydrite	1794	1823	
Shale & Shells	1823	2000	
Anhydrite & Shale	2000	2395	
Anhydrite	2395	2462	
Anhydrite & Shale	2462	2594	
Lime & Shale	2594	2640	Show of Gas @ 2635' Set 7" OD w/600 sz
Lime & Shale	2640	2665	
Lime	2665	2755	TD

125 Iner set

2635 2755
 125

 2630

125' Iner set

J B Newner

AM Mitchell 9-1067

Skyline 11520
11515

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 30 1964
 CONSERVATION DIVISION
 Wichita, Kansas

TO: Walter Kuhn

DATE: 11-13-58

FROM: M.L. Dale

C/ S/ E/ y 29-32-36

SUBJECT: Neuner-Kuhn #1 Workover.

- 9-24-58: Measured well and found Fluid at 400' and sand at 2098'.
 9-26-58: Moving in cable tools.
 9-27-58: Rigging up cable tools and running 6-5/16" swage to check casing. Found casing out to gauge.
 9-28-58: Moved in pulling unit and run -56 Jts of 5 1/2" OD 14# casing with Larkin 7" OD X 5 1/2" hookwall packer on bottom. 1824' of casing with packer set at 1830'. Swabbed 400' of water.
 9-29-58: Rigging up and cleaning out sand from 2030' to 2060'.
 9-30-58: Cleaning out sand from 2060 to 2135' with sandpump and tools.
 10-1-58: Cleaning out from 2135 to 2225' with sandpump and tools.
 10-2-58: Cleaning out from 2225' to 2250'.
 10-3-58: Cleaning out from 2250' to 2350' small show of gas.
 10-4-58: Cleaning out from 2350' to 2400'.
 10-5-58: Cleaning out from 2400' to 2465'.
 10-6-58: Cleaning out from 2465' to 2550' Increase in gas.
 10-7-58: Cleaning out from 2550' to 2625' Had to load hole with water.
 10-8-58: Cleaning out from 2625' to 2700'. Hole bridged on top of liner.
 10-9-58: Run bailer and kicked well off. Blowing well.
 10-10-58: Checked TD and found well O.K. Gauged -8,500 MCF.
 10-11-58: Tearing down tools and moving out.
 10-12-58: Moving Rig to Yard.

Casing History:

- 5 1/2" casing from 0' to 1824'
 5 1/2" X 7" OD larkin packer from 1824' to 1830'
 7" OD from 1830' to 2630'
 5 1/2" OD Liner from 2630' to 2755' TD.

 M.L. Dale

RECEIVED
 STATE CORPORATION COMMISSION

SEP 30 1964

CONSERVATION DIVISION
 Wichita, Kansas