



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co. Inc.

Complete Address Suite 800-200 W. Douglas Wichita, Ks. 67202

Lease Name Chitwood Well No. G-5

Location C SW/NE/SE Sec. 22 Twp. 28 Rge. 12 (E) (W)

County Pratt Total Depth 4455

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 5:00PM Day 24 Month 2 Year 1970

The above well was plugged as follows:

344 ft. of 8 5/8 surface pipe circulated with 250 sacks cement. 4421
ft of 5 1/2 long string cemented with 200 sacks. Top Perf. 4411 ft.
Sand back to 4380 ft, 5 sacks cement, with bailer. Pulled 3200 ft of
5 1/2. Fill hole to 250 ft, 10 ft rock bridge, 25 sacks cement. Mud
to 40 ft, 10 ft rock bridge. 10 sacks cement to top of surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/27/70
INV. NO. 1502-W