

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Seward County, Sec. 20 Twp. 32 Rge. 31 (SW) (W)



Locate well correctly on above Section Flat

Location as "NE/CNWxSWx" or footage from lines \_\_\_\_\_  
Lease Owner Texas Energies, Inc.  
Lease Name Roehr #1 Well No. \_\_\_\_\_  
Office Address Amarillo, Texas 79109  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed May 1973  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved February 22 1974  
Plugging commenced 3/22/74 19\_\_\_\_  
Plugging completed 3/26/74 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production June 1973  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Edgar Fayer  
Producing formation St. Gen Depth to top 5809 Bottom 5840 Total Depth of Well 5903 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1384'	none
				5 1/2"	5901	1745'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 2 sacks hulls, 20 sacks cement to 4600'. Shot pipe at 1746' and pulled 54 joints. Set 10' rock bridge at 600' and ran 35 sacks cement. Mudded to 45' and set 10' rock bridge, ran 15 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
CHASE, KANSAS

(Address)

Subscribed AND SWORN TO before me this 29th day of March, 1974

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

[Signature]  
Notary Public.

DRILLERS LOG

ROEHR NO. 1

CASING RECORD:	OPERATOR: Texas Energies, Inc.	DESCRIPTION:
8-5/8" @ 1384' w/700 sax cement	CONTRACTOR: Sage Drilling Co.	C SW NE Sec. 20-32S-31W Seward County, Kansas.
TOTAL DEPTH:	COMMENCED: April 12, 1973	
Rotary 5900'		
Log 5903'	COMPLETED: April 25, 1973	ELEVATION: 2801KB


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	284	
Sand & Red Bed	284	644	
Red Bed	644	860	
Red Bed & Sand	860	1390	
Shale & Red Bed	1390	1710	
Shale	1710	2200	
Shale & Lime	2200	2700	
Lime & Shale	2700	5903	5 1/2" set @ 5902' w/150 sax cement

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 22 1974  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Clarence Michael  
Clarence Michael



subscribed and sworn to before me this 27th day of April, 1973.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.