


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 14 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name RAYMOND OIL CO., INC.

Complete Address 410 4<sup>th</sup> NATL BANK BLDG WICHITA, KS 67202

Lease Name CHITWOOD UNIT Well No. E-3

Location SW-C-SW-SE Sec. 22 Twp. 28 Rge. 12 (E) (W) ✓

County PRATT Total Depth 4480

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor KNIGHT CASING PLUGGING Co. INC.

Address BOX 405 CHASE, KS. License No. 624

Operation Completed: Hour 1:30 P.M. Day 12 Month 1 Year 1970

The above well was plugged as follows:

332 FT OF 9" SURFACE PIPE CIRCULATED WITH CEMENT  
4479 FT OF 5 1/2" LONG STRING, TOP PERFORATION 4404  
SAND TO 4385 5 SCKS CEMENT WITH RAHER 2610 FT  
OF 5 1/2" PULLED. MUD TO 250 FT. 10 FT ROCK BRIDGE  
+ 25 SACKS CEMENT. MUD TO 40 FT, 10 FT ROCK  
BRIDGE 10 SACKS CEMENT TO SURFACE

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. Russell Bilerstein  
Well Plugging Supervisor

DATE 1/14/70  
INV. NO. 1245-W