

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address Suite 800 200 W Douglas Wichita, Ks 67202

Lease Name Chitwood Unit Well No. G 3

Location SW/C/NW/SE Sec. 22 Twp. 26 Rge. 12 (E) (W) X

County Pratt Total Depth 4480

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:AM Day 6 Month 2 Year 1970

The above well was plugged as follows:

303 ft of 8 5/8 surface pipe cemented sith 200 sacks 4479 ft of 5 1/2
long string cemented with 250 sacks Top per 4396 ft. Sand back to
4380 ft, 5 sacks cement with bailer. 3030 ft of 5 1/2 pulled. Fill
hole 250 ft, 10 ft rock bridge, 25 sacks cement. Mud to 40 ft, 10
ft rock bridge. 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M Russell Bikerstein
Well Plugging Supervisor

DATE 2/9/70
INV. NO. 1392-W