

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-21347 - 0000

LEASE NAME BLAKE "A"

WELL NUMBER 1

1250 Ft. from S Section Line

1250 Ft. from E Section Line

SEC. 21 TWP. 32 RGE 41 ( E ) or (W)

COUNTY MORTON

Date Well Completed 3-14-95

Plugging Commenced 10-05-95

Plugging Completed 10-08-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-04-95 (date)

by STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2420

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	775'	NONE
				5-1/2"	2398'	680'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
MIRU PUMP TRUCK & CSG PULLERS, PMP 2 SXS HULLS & 25 SXS CMT DWN CSG FROM 2190-1990' OVER PERFS. PULL FREE POINT ON 5-1/2" AND CUT OFF AT 680' SPOT 60 SXS CMT FROM 680-480' PULL 5-1/2" TO 33' PMPD 10 SXS FROM 33-3' PULL 5-1/2" TO SURF. CUT 8 5/8" OFF 3 FEET BELOW GL, CAP & PERMANENTLY INSCRIBE WELL NAME AND DATE PLUGGED ON CAP. RDHO CASING PULLERS. WITNESSED BY KCC REP STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEWARD, ss. OCT 20 1995

DAVID W. KAPPLE (Employee of Operator) or (xxxxxx) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and that the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of October, 1995



L. Marc Harvey  
Notary Public

My Commission Expires \_\_\_\_\_