

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21621-0001

LEASE NAME Johns

2-524

WELL NUMBER _____

2310 Ft. from ^N Section Line

330 Ft. from ^W Section Line

SEC. 24 TWP. 32S RGE. 41 (E) or (W)

COUNTY Morton

Date Well Completed 1/1/01

Plugging Commenced 5/26/01

Plugging Completed 5/26/01

LEASE OPERATOR Presco Western, LLC

ADDRESS 1775 Sherman Street, Suite 2950 Denver, CO 80203

PHONE# (303) 864-1881 ext 103 OPERATORS LICENSE NO. 32309

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 25, 2001 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom T.D. 5610'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Surface	.		8 5/8"	1737	0 JUN 20 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Well was plugged using 225 sacks 60/40 POZ w/ 6% gel 1/4# floseal as follows:
Plug no 1-3000' w/ 100 sks; Plug No 2-1750' w/ 50 sks; Plug No. 3-500' w/ 40 sks;
Plug No. 4-40' w/ 10 sks; mousehole w/10 sks. Rathole w/15 sks.

Name of Plugging Contractor Cheyenne Drilling License No. 5382

Address 3728 W. Jones Ave. Garden City, KS 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Presco Western, LLC

STATE OF Colorado COUNTY OF Denver, ss.

Richard J. Gray

(Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) _____

(Address) 1775 Sherman Street, Suite 2950 Denver, CO 80203

SUBSCRIBED AND SWORN TO before me this 18th day of June, 2001.

[Signature]
Notary Public

My Commission Expires: 11-9-04

OR

ALLIED CEMENTING CO., INC. 5290

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>5/26/01</u>	SEC. <u>24</u>	TWP. <u>32s</u>	RANGE <u>41W</u>	CALLED OUT	ON LOCATION <u>7:00 AM</u>	JOB START <u>8:00 AM</u>	JOB FINISH <u>11:15 AM</u>
LEASE <u>Johns</u>		WELL # <u>2-524</u>		LOCATION <u>Richfield 2 1/2 E 3/4 E 1/2 S</u>		COUNTY <u>Morton</u>	STATE <u>K.S.</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Cheyenne #1
 TYPE OF JOB Rotary Plug
 HOLE SIZE 7 1/2 T.D.
 CASING SIZE _____ DEPTH _____
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2 16.60" DEPTH 3000
 TOOL _____ DEPTH _____
 PRES. MAX 250 MINIMUM 50
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER Sam

CEMENT
 AMOUNT ORDERED 225 sks 60/40 + 60 gel 4" Flo-seal

COMMON	<u>135 sks</u>	@ <u>7.95</u>	<u>1059.75</u>
POZMIX	<u>90 sks</u>	@ <u>3.55</u>	<u>319.50</u>
GEL	<u>125 sks</u>	@ <u>10.00</u>	<u>1200.00</u>
CHLORIDE		@	
<u>Flo-seal</u>	<u>56"</u>	@ <u>1.40</u>	<u>78.40</u>
		@	
		@	
		@	
		@	
HANDLING	<u>239 sks</u>	@ <u>1.10</u>	<u>262.90</u>
MILEAGE	<u>4 1/2 sk/mi</u>		<u>430.20</u>

EQUIPMENT

PUMP TRUCK CEMENTER Max
 # 191 HELPER Andrew
 BULK TRUCK
 # 291 DRIVER Fuzzy
 BULK TRUCK
 # _____ DRIVER _____

TOTAL 2270.75

REMARKS:

SERVICE

Spot Plugs 100 sks @ 3000 FT
50 sks @ 1750 FT
40 sks @ 500 FT
10 sks @ 40 FT
10 sks Mouse Hole
15 sks Rat Hole

DEPTH OF JOB 3000
 PUMP TRUCK CHARGE _____ 630.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 45 mi @ 3.00 135.00
 PLUG _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL 765.00

CHARGE TO: Presco Western
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE 3089.75
 DISCOUNT 303.57 IF PAID IN 30 DAYS
2732.18

SIGNATURE Philip Loyd

PRINTED NAME