

15-129-20058-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Morton County, Sec. 27 Twp. 32S Rge. (E) 41 (W)
Location as "NE/CNW/SW" or footage from lines C NE 1/4 SW 1/4
Lease Owner Ladd Petroleum Corporation
Lease Name Lemon "C" Well No. 1
Office Address P. O. Box 520, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 23 19 70
Application for plugging filed November 23 19 70
Application for plugging approved November 24 19 70
Plugging commenced November 24 19 70
Plugging completed November 24 19 70
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5050 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1417'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from 5050' to 1000'
Cement from 1000' to 900' with 35 Sacks Cement
Mud from 900' to 45'
Cement from 45' to 0' with 15 Sacks Cement

Plugged @ 9:00 a.m.

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 - 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield
Address 300 West Douglas, Suite 500, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
300 W. Douglas, Suite 500, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 30th day of November, 19 70

October 22, 1972

Carol Jean Noel
Carol Jean Noel
Notary Public.



LEASE: LEMON "C" #1
OWNER: LADD PETROLEUM COMPANY
CONT: EARL F. WAKEFIELD
COMM: 11-13-70
COMP: 11-23-70

LOCATION: C NE/4 SW/4
SECTION 27-32S-41W
MORTON COUNTY, KANSAS
CASING: 8 5/8" SET @ 1417'

Surface Clay & Hard Sand	275
Red Bed & Sand	695
Sand & Red Bed	1250
Red Bed - Anhydrite	1418
Red Bed & Anhydrite	1445
Anhydrite, Shale & Shells	1745
Shale	1985
Shale & Shells	2305
Lime & Shale	2420
Shale - Lime	2585
Lime & Shale	2725
Lime - Shale	3060
Lime & Shale	3685
Lime - Shale	3800
Lime & Shale	4075
Lime - Shale	4325
Lime & Shale	4435
Lime - Shale	4540
Lime & Shale	4769
Shale - Lime	4930
Shale	5050
R.T.D.	5050

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 - 1970
CONSERVATION DIVISION
Wichita, Kansas

I, Gordon L. Koelling, do hereby certify that this is a true and correct log on the Lemon "C" #1, located C NE/4 SW/4 of Section 27-32S-41W, Morton County, Kansas, as shown by the daily drilling reports.

EARL F. WAKEFIELD

BY Gordon L. Koelling
Gordon L. Koelling

Subscribed and sworn to before me this 30th Day of November, 1970.

My Commission Expires:
October 22, 1972

Carol Jean Noel
Carol Jean Noel
Notary Public

