


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Kingman County. Sec. 30 Twp. 30S Rge. 6W. E2W  
Location as "NE/CNW1/4SW1/4" or footage from lines

C - NE NE  
Lease Owner Halliburton Oil Producing Company  
Lease Name Naffziger Well No. 1  
Office Address 300 Cameron Bldg., 2915 Classen Blvd.,  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole OK City, OK  
Date Well completed April 10, 1978  
Application for plugging filed Verbal Application 1978  
Application for plugging approved Verbal Approval 1978  
Plugging commenced April 10, 1978  
Plugging completed April 10, 1978  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation Depth to top Bottom Total Depth of Well 4,670  
Show depth and thickness of water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION  
OIL, GAS AND WATER RECORDS  
APR 17 1978  
CONSERVATION DIVISION  
Wichita, Kansas

FORMAT	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,670 ft. (rotary total depth) to 250 ft. Set plug at 250 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 250 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 1978

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires June 30, 1978



KANSAS DRILLERS LOG

COMPANY Halliburton Oil Producing Company  
FARM Naffziger NO. 1

SEC. 30 T. 30S R. 6W  
LOC. C - NE NE

COUNTY Kingman

ROTARY TOTAL DEPTH 4,670'  
COMM. March 30, 1978  
CONTRACTOR H-30, Inc.  
ISSUED April 14, 1978

COMP. April 10, 1978

CASING

10 3/4"  
8 5/8" Set at 249' cemented w/200 sxa cement  
5 1/2"  
4 1/2"

ELEVATION 1,511 K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed, Rock and Shale	250'
Red Bed	490'
Shale	1,055'
Lime and Shale	4,670'
Rotary Total Depth	4,670'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas }  
County of Sedgwick } SS:

Suscribed and Sworn to before me, a Notary Public in and for said county and state this 14th day of April, 1978.

*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978

RECEIVED  
STATE CORPORATION COMMISSION

APR 17 1978

CONSERVATION DIVISION  
Wichita, Kansas

