

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D.J. Stone 15-129-10003-0001

Complete Address: 217 Town & Country Village, Palo Alto, California 94301

Lease Name Hanke Well No. 1

Location: SW SE Sec. 32 Twp. 31 Rge. 41 W (W)

County Morton Total Depth 5344'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 6:30PM Day 9 Month 6 Year 1969

The Above well was plugged as follows:

8 5/8" to 1504' circulated w/ cement. 5 1/2" to 5344' cemented.

Top perforations 5242' Plug bottom w/ 20 sacks cement.

Top of cement 5050' Mud 5050' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3032' of 5 1/2" Casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edmund E. ...*
Well Plugging Supervisor

DATE 6/13/69
INV. NO. 9938-W