



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-175-00426-0000

RECEIVED  
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Michaelis of Graham-Michaelis Drill. Co. has this

date requested permission to plug the following described well:

Mr. Michaelis guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drill. Co.

Complete Address: 211 N. Broadway. Wichita, Kansas

Lease Name: Schmidt "A" Well No. # 1

Location: C SW/4 Sec. 7 Twp. 31 Rge. 31 (E)/(W)

County Seward Total Depth 2708' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Michaelis was instructed to plug the well as follows:

8 5/8"-575' Circulated w/cement. 5 1/2"-2707' Cemented.

Perforations 2506' to 2551'. Plug bottom w/20 Sax.cement top cement. 2408'

Mud 2408' to 575' Spotted 35 Sax.cement 575' to 475'

Mud 475" to 45' Plug, Hulls, 15 Sax.cement 45' to 0

Very truly yours,

*Hugh Scott*  
Conservation Division Agent