



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-175-20601-8000

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1982

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Wayne King of Du Mar Rig (Rig 3) has this date requested permission to plug the following described well:

Operator's Full Name: Kennedy + Mitchell, Inc.

Complete Address: 215 one Twenty Bldg. Wichita, Mo. 67202

Lease Name: Jolly Well No. 45-700

Location: C-NW Sec. 35 Twp. 34 Rge. 22 (E) (W)

County: Seward Total Depth: 6492 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. King is instructed to plug the well as follows:

8 5/8" - 1566 FT SR. CUL w/ 600 st 65 Formix - 6% Gel. - 2% Ca-Cl.

Order 210 st 50 Formix 4% Gel. - 2% Ca-Cl. + 8 5/8" Plug.

Spot with Drill Stem with Heavy Mud Between all Plugs.

1st Plug @ 3050 FT w/ 25 st cnt.

2nd Plug @ 2570 FT w/ 35 st cnt.

3rd Plug @ 1560 FT w/ 60 st cnt.

4th Plug @ 540 FT w/ 50 st cnt.

5th Plug - sand bridge - shale plug @ 40 FT to 0 w/ 10 st cnt.

10th In Rat Hole (circulate)

10th In Mouse hole (circulate)

Very truly yours,
Jefferson Schmidt
Conservation Division Agent

(By Jefferson Schmidt)