



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-025-20538-0000

RECEIVED  
STATE CORPORATION COMMISSION

DEC - 8 1981

CONSERVATION DIVISION  
Wichita, Kansas  
Rig #6

Dear Sir:

Mr. Mike Rempic of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Imperial Oil Co.

Complete Address: 720 Fourth Financial Center Wichita, Kansas 67202

Lease Name: Emel R. Well No. 1-4

Location: 60' N + 55' E of W 1/2 of SE NW Sec. 4 Twp. 31 Rge. 21 W (E) (W)

County: Cherokee Total Depth: 5245'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Rempic was instructed to plug the well as follows:

There is 626' of 8 5/8" surface casing cement circulated. The annular space is at 1080'. With hole full of heavy mud, 1st plug 1000' with 50 lbs of cement. 2nd plug pushed rubber plug to 600' and pumped 40 lbs on top of it. 3rd plug at 40' to 0' with 10 lbs of cement on solid bridge. They pumped 5 lb cement in rat hole. Plugging accomplished by Sun cementing of Great Bend Kans. Cement used was common cement with 2% Jell + 2% C @.

Very truly yours,

Paul Luther  
Conservation Division Agent