

99

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
15-129-60035-0000
RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company
Complete Address 915 Union Nat'l Bldg., Wichita, Kansas 67202
Lease Name Hayward Well No. 1-23
Location C NE Sec. 23 Twp. 31 Rge. 42 (E) (W)
County Morton Total Depth 5335'
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Sargents Casing Pulling Co.
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 5:00Pm Day 9 Month 6 Year 1971

The above well was plugged as follows:

8 5/8" to 1509' circulated w/ cement. 5 1/2" to 5318' cemented.
Top perforations 2886' Plug bottom w/ 30 sacks cement.
Top of cement 2619' Mud 2619' to 1000'
Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'
Plug. Hulls & 15 sacks cement 45' to 0'. Company Pump
Pulled 2316' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6-15-71
INV. NO. 3866-W