



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas

Well Plugging Authority
dated Nov 22, 1974.
15-129-20164-5000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Besen Corporation
Complete Address 1130 Nichols-KS B+T Bldg, Wichita, KS
Lease Name Hayward Well No. 1-23
Location C. EL-NE. Sec. 23 Twp. 31 Rge. (E) (W) 42
County Wichita Total Depth 3342 3338
Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling
Address Box 364, Great Bend, KS-67530 License No. 399
Operation Completed: Hour 12:00^{noon} Day 27th Month Nov Year 1974

The above well was plugged as follows:

There was 746 ft of 8 1/8" surface casing set with 500 sack cement. There was 3337 ft of 4 1/2" set with 300 sack 60-40% mix. Perforation was from 2438-2400. Filled with sand to 2438. 3 sack cement from 2438-2400. used 120 sack of cement from 647 ft to O. There was 1130 ft of 4 1/2" pipe salvaged.

I hereby certify that the above well was plugged as herein stated.

Signed: Clarence T. Thomas
Well Plugging Supervisor

INVOICED

DATE 12/4/74
INV. NO. 385-W

DEC 2 1974

TELEPHONE: 222-8457
222-1142

JIM SNYDER DRILLING COMPANY
DENVER CLUB BUILDING
518 - 17TH STREET
DENVER, COLORADO 80202

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1974

CONSERVATION DIVISION
Wichita, Kansas

November 27, 1974

15-129-20164-0000

The Beren Corporation
1130 Vickers KST&B Building
Wichita, Kansas 67202

Re: #1-23 Hayward Well
Section 23-Twp. 1 South-Rge. 42 West
Morton County, Kansas

Gentlemen:

In accordance with your telephone request regarding the formations encountered during the drilling operations of the captioned well, we submit the following detail as outlined on our daily drilling reports:

| <u>Footage</u> | <u>Formation</u> |
|---------------------|------------------|
| 100' to 383' | Shale |
| 383' to 2800' | Shale and Sand |
| 2800' to 3338' T.D. | Shale and Lime |

We trust this information meets your requirements to complete your records.

Yours very truly,

JIM SNYDER DRILLING COMPANY

Tom Snyder
Tom Snyder

fr