

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUL 5 1972

CONSERVATION DIVISION  
Wichita, Kansas

15-129-10094-0008

Operator's Full Name Sargent's Casing Pulling

Complete Address Box 506, Liberal, Kansas

Lease Name Baughman Well No. 1

Location C SW Sec. 28 Twp. 31 Rge. 42 (E) (W)

County Morton Total Depth 3540'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Sargent Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00PM Day 28 Month 6 Year 1972

The above well was plugged as follows:

8 5/8" to 558' circulated w/ cement. 5 1/2" to 3195' cemented.

Top perforations 2741' Plug bottom w/ 20 sacks cement.

Top of cement 2550' Mud 2550' to 550'

Spotted 35 sacks cement 550' to 450' Mud 450' to 45'

Plug. Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 1224' of 5 3/4" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/5/72  
INV. NO. 5988-W