

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-129-10069-0000

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Colorado Oil & Gas Corporation

Complete Address: Box 158, Liberal Kansas

Lease Name Schrader Well No. 1

Location C SW Sec. 31 Twp. 31 Rge. 42 (E) (W)

County Morton Total Depth 3630'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Service

Address: Box 506, Liberal Kansas License No. 5114

Operation Completed: Hour 5:30PM Day 30 Month 12 Year 1966

The Above well was plugged as follows:

103/4" to 684' circulated w/ cement. 7" to 3629' Cemented.

Top Perforations 3096' Plug bottom w/ 20 sacks cement.

Top of cement 3000' Mud 3000' to 500'

Spotted 40 sacks cement 500' to 375' Mud 375' to 40'

Plug, Halls & 10 sacks cement 40' to 0' Company Pump

Pulled 1006' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 1/3/67

INV. NO. 4539-W