

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-129-10168-0000

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1962  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Superior Oil Company

Complete Address: Byrant Petr. Bldg. Box 809, Tyler, Texas.

Lease Name Martin Well No. #1

Location C SE Sec. 35 Twp. 31 Rge. 42 (X) (W)

County Morton Total Depth 3326

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Sargent Casing Pulling Service

Address: 121 West 9th Street, Liberal, Kansas License No. 511

Operation Completed: Hour 6PM Day 8 Month 9 Year 62

The Above well was plugged as follows:

8 5/8" 764' Circulated w/cement. 7" 3326' Cemented.

Plug back to 2873' Perforations 2815'

Plug bottom w/sand and 5 sax.cement 2873' to 2800'

Heavy mud 2800' to 700'

Plug and 35 sax.cement 700' to 590'

Heavy mud 590' to 45'

Plug and 15 sax. cement to surface. (Pulled 1147' 7" pipe.)

(Company Pump)

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9/11/62  
INV. NO. 5661-w

Signed: [Signature]  
Well Plugging Supervisor