

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-129-10181-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1962

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Whitestone Petroleum Corp.

Complete Address: 900 Vaughn Bldg. Dallas, Texas

Lease Name M.R. Johns Well No. # 1

Location C NE Sec. 12 Twp. 31 Rge. (E) (W) 42

County Morton Total Depth 5600'
5520'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service.

Address: Liberal, Kansas License No. # 511

Operation Completed: Hour 4PM Day 8 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 1649' Circulated w/cement. 4 1/2" 5518' Cemented.

Baker steel plug set at 5160' and 6 sax.cement 5160' to 5100'

Top of perforation 4120'

Sand 5100' to 4000'; 5 sax.cement 4000' to 3950', Mud 3950' to 600'

Plug and 35 sax.cement 600' to 500', Mud 500' to 50'

Rock bridge 50' to 40', 15 sax.cement 40' mto surface.

Pulled 2806' 4 1/2" Piped. Company pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12/12/62
INV. NO. 6209-11