

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-129-10162-0000

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Superior Oil Company

Complete Address Box 200, Gasper, <sup>WY</sup>Wyoming 82601

Lease Name Garner Unit Well No. 1

Location C NW Sec. 14 Twp. 31 Rge. 42 ~~(E)~~ (W)

County Morton Total Depth 5212'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 20 Month 4 Year 1970

The above well was plugged as follows:

8 5/8" to 1535' circulated w/ cement. 5 L/2" to 5210' cemented.

Top perforations 5140' Plug bottom w/ 20 sacks cement.

Top of cement 4000' Mud 4000' to 900'

Spotted 35 sacks cement 900' to 800'. Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2710' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated

RECEIVED  
STATE CORPORATION COMMISSION

Signed: Edward J. Eves  
Well Plugging Supervisor

INVOICED

APR 22 1970

CONSERVATION DIVISION  
Wichita, Kansas

DATE 4/22/70

INV. NO. 1961-W