

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-129-00027-0000

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1964

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J.M. Huber Corporation

Complete Address: Box 987 Liberal, Kansas

Lease Name Collingwood Well No. # 1

Location C NE/4 Sec. 11 Twp. 31S Rge. (E) (W) 42

County Morton Total Depth 5323'

Abandoned Oil Well X Gas Well - Input Well - SWD Well - D & A X

Other well as hereafter indicated: -

Plugging Contractor: Daco Lease & Well Servicing Co.

Address: Borger, Texas License No. 138

Operation Completed: Hour 8 PM Day 9 Month 3 Year 64

The Above well was plugged as follows:

8 5/8"-1520' Circulated w/cement. 5 1/2"-5321' Cemented.

Plyg. back to 2955' w/cement. Perforation 2873' to 2910'

Plug bottom w/20 Sax.cement stop plug at 2775'. Mud 2775' to 700'

35 Sax.cement 700' to 595' Mud 595' to 45'

15 Sax.cement 45' to 0

Pulled 2305' 5 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/11/64

INV. NO. 8445-11