

15
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-175-66426-0000

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Graham-Michaelis Drill. Co.

Complete Address: 211 N. Broadway. Wichita, Kansas

Lease Name Schmidt "A" Well No. # 1

Location C SW/4 Sec. 7 Twp. 31 Rge. 31 (E)/(W)

County Seward Total Depth 2708'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 1 Month 8 Year 64

The Above well was plugged as follows:

8 5/8"-575' Circulated w/cement. 5 1/2"-2707' Cemented.

Perforations 2506' to 2551' Plug bottom w/20 Sax.cement top cement 2408'

Mud 2408' to 575' Spotted 35" ax.cement 575' to 475'

Mud 475' to 45' Plug, Hulls, 15 Sax.cement 45' to 0

Pulled 1212' 5 1/2" pipe. Cut surface pipe off 5' below ground level.

Company pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/3/64

INV. NO. 9598-W

Signed: [Signature]
Well Plugging Supervisor