

KANSAS

Form CP-3 (REV. 6-4-68) COMMISSION

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

JUL 25 1976  
6-25-76  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 175-20,289 (of this well) <sup>00-00</sup>

Operator's Full Name Imperial Oil Co.  
Complete Address 720 4th Financial Center, Wichita, KS  
Lease Name Elliott Well No. 1-25  
Location C. SW. NE. Sec. 25 Twp. 31 Rge. (E) (W) 31  
County Seward Total Depth 657'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated Last hole  
Plugging Contractor Sage Drilling Co. Inc  
Address 500 Bitting Bldg, Wichita, KS License No. \_\_\_\_\_  
Operation Completed: Hour 7:30 PM Day 24 Month June Year 1976

The above well was plugged as follows:

There was no surface casing. Last  
circulation. 1st plug at 500' with  
50 sacks of cement. Filled with heavy  
mud to 40'. 2nd plug from 40' with  
15 sacks. 5 sacks in rat hole. Accomp  
lished by Halliburton, Liberal, Kans.  
Will skid rig 125' East & drill  
New hole.

I hereby certify that the above well was plugged as herein stated

INVOICED

DATE 7-1-76

INV. NO. 3415-44

Signed: Clarence Thomas  
Well Plugging Supervisor

DRILLERS LOG


ELLIOTT NO. 1-25

CASING RECORD: OPERATOR: Imperial Oil Company DESCRIPTION:  
8-5/8" set @ 1692' CONTRACTOR: Sage Drilling Co. C SW NE  
w/800 sax cement COMMENCED: June 25, 1976 Sec. 25-31S-31W  
TOTAL DEPTH: COMPLETED: July 10, 1976 Seward Co., Kansas  
5890' ELEVATION: 2792KB

| <u>FORMATION</u>            | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u>                                                                                              |
|-----------------------------|-------------|-----------|-------------------------------------------------------------------------------------------------------------|
| Sand & Red Bed              | 0           | 738       | RECEIVED<br>STATE CORPORATION COMMISSION<br><br>SEP 27 1976<br><br>CONSERVATION DIVISION<br>Wichita, Kansas |
| Red Bed & Sand              | 738         | 1487      |                                                                                                             |
| Shells, Red Bed & Anhydrite | 1487        | 1702      | D&A                                                                                                         |
| Anhydrite & Shale           | 1702        | 1725      |                                                                                                             |
| Shells & Shale              | 1725        | 2585      |                                                                                                             |
| Shale & Anhydrite           | 2585        | 2690      |                                                                                                             |
| Anhydrite & Dolomite        | 2690        | 3100      |                                                                                                             |
| Dolomite & Shale            | 3100        | 3307      |                                                                                                             |
| Lime & Shale                | 3307        | 5890      |                                                                                                             |


I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By 

T. M. McCaul, Jr.

Subscribed and sworn to before me this 15th day of July, 1976.

  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1978.

