

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Ks. 67202

API Number 15 129 20.441 <sup>0000</sup> (of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Wichita, Kansas

Lease Name Stevens D. Well No. 1

Location 1650 FNL + 1650 FAD, NE 1/4 <sup>(NW SE NE)</sup> Sec. 2 Twp. 31 Rge. 41 (E) W

County Morton Total Depth 5470

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereafter indicated Abandoned 5/29/80.

Plugging Contractor Halliburton Cementing

Address Liberal, Kansas License No.     

Operation Completed: Hour 4:30 PM Day 11 Month Aug Year 1980.

The Above well was plugged as follows:

There was 1578' of 8/8" surface casing  
1st plug at 3250' with 75 lbs cement. 2nd  
plug at 2850' with 75 lbs cement. 3rd  
plug at 1500' with 50 lbs cement. 4th  
plug at 750' with 75 lbs cement. 5th plug  
at 400' with 10 lbs cement. Mud circulated  
through 2 3/8" tubing. Accomplished by  
Halliburton Cementing.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 8-14-80

INV. NO. 28101-W

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1980  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Charles Thomas  
Well Plugging Supervisor

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

5-129-20441-000

Stevens "D" #1 <sup>43</sup>  
 1650' FNL & 1650' FWL Sec 2-31S-41W  
 Morton County Kansas

Commenced: 5-10-80

Completed: 5-30-80

OPERATOR: Texas Oil & Gas Corporation

Depth		Formation	Remarks
From	To		
0	818	Sand-Shale	Ran 36 jts of 24# 8 5/8" csg set @ 1528 KB Cemented w/400 sks 35/65 Posmix 6% Gel 2% CC + 150 sks Class H 3% CC PD @ 9:00 p.m. 5-13-80
818	1100	Redbed-Anhy	
1100	1532	Anhy-Shale	
1532	1549	Shale	
1549	1753	Redbed-Shells	
1753	2408	Shale-Sand	
2408	2568	Shale-Redbed-Lime Stks	
2568	3214	Shale-Lime	
3214	4240	Lime-Shale	
4240	4473	Shale-Lime	
4473	4793	Lime-Shale	
4793	4891	Lime-Shale-Sand	
4891	5375	Lime-Shale	
5375	5470	Shale-Sand-Quartz	
	5470 - TD		Plugged w/Swage & Valve

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above  
 Drillers' Well Log is true and correct to the best of my knowledge and belief and  
 according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 4th day of June, 1980.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

NOTARY PUBLIC  
 STATE OF KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 18 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas