

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co. Inc.
Complete Address 200 W. Douglas Wichita, Ks
Lease Name Chitwood Unit Well No. M-12
Location NW/NE/NE Sec. 23 Twp. 28 Rge. 12 (E) W
County Pratt Total Depth 4427
Abandoned Oil Well ☒ Gas Well ☐ Input Well ☒ SWD Well ☐ D & A ☐
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co. Inc.
Address Box 405 Chase, Ks License No. 436
Operation Completed: Hour 4:00 PM Day 11 Month 2 Year 1971

The above well was plugged as follows:

344 ft of 10 3/4 surface pipe cemented with 250 sacks. 4420 ft of
5 1/2 long string cemented with 400 sacks. Open hole. Sand back to
4400 ft, 5 sacks cement with bailer. Pulled 2930 ft of 5 1/2. Set 20
ft rock bridge at 340 ft, & 40 sacks cement. Mud to 40 ft, & 15
sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Russell B. Burtis*
Well Plugging Supervisor

DATE 2/17/71INV. NO. 3340-W