

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 4 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address Suite 800 200 W. Douglas Wichita, Ks

Lease Name Chitwood Unit Well No. H-8

Location CNE/NW/SW Sec 23 Twp. 28 Rge 12 (E) (W) X

County Pratt Total Depth 4500

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 5:00 PM Day 2 Month 2 Year 1970

The above well was plugged as follows:

300 ft of 8 5/8 surface pipe circulated with 225 sacks cement.  
4493 ft of 5 1/2 long string cemented with 300 sacks cement. Top per.  
4361 ft, sand back to 4350 ft, 5 sacks cement with bailer. 2700 ft  
of 5 1/2 pulled. Fill hole to 250 ft, 10 ft rock bridge, 25 sacks ce-  
ment. Mud to 40 ft, 10 ft rock bridge. 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: G. Russell Behrman  
Well Plugging Supervisor

INVOICED

DATE 2/4/70  
INV. NO. 1363-W