

KANSAS

*PL*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1972  
09-06-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 200 W. Douglas Wichita, Ks

Lease Name Chitwood Well No. 3-J-8

Location NE/SW/NW Sec. 23 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4474

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:00 AM Day 5 Month 9 Year 1972

The above well was plugged as follows:

308 ft 8 5/8 surface pipe cemented with 200 sacks. 4470 ft 5 1/2 long  
string cemented with 200 sacks. Top perf. 4280 ft. Push plug to  
4200 ft. Sand to 4175 ft, 5 sacks cement with bailer. Pulled 2435 ft  
5 1/2. Set 10 ft rock bridge at 240 ft. Fill hole with 4 yds redimix  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: P. Russell Biberstein  
Well Plugging Supervisor

INVOICED

DATE 9/6/72

INV. NO. 6279-W