

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S RECEIVED
STATE CORPORATION COMMISSION

FEB 9 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Raymond Oil Co. Inc

Complete Address 200 W Douglas Wichita, KS

Lease Name Chitwood Well No. 1-7

Location SW/SW/NW Sec. 23 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4460

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Voth Casing Pulling Co

Address 715 S. A St. Arkansas City, KS License No. 684

Operation Completed: Hour 11:00 AM Day 7 Month 2 Year 1973

The above well was plugged as follows:

316 ft 9" surface cemented with 200 sacks. 4459 ft 5 1/2 long string
cemented with 250 sacks. Open hole. Sand to 4420 ft, 5 sacks cement
with bailer. Pulled 2060 ft 5 1/2. Set 10 ft rock bridge at 240 ft.
Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed:
Well Plugging Supervisor

INVOICED

DATE 2/12/73

INV. NO. 6962-W