

KANSAS

2

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 200 W. Douglas Wichita, Ks

Lease Name Chitwood Well No. 9

Location SW/SE/NW Sec. 23 Twp. 28 S Rge. 12 (E) (W) W

County Pratt Total Depth 4460

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 4 36

Operation Completed: Hour 4:00 PM Day 6 Month 2 Year 1971

The above well was plugged as follows:

312 ft of 9" surface pipe cemented with 200 sacks. 4460 ft of 5½
long string cemented with 300 sacks. Top perf. 4407 ft. Sand back
to 4400 ft, 5 sacks cement with bailer. Pulled 2960 ft of 5½. Set
10 ft rock bridge at 275 ft., & 35 sacks cement. Mud to 40 ft,
10 ft rock bridge & 15 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. Russell Bidart*
Well plugging Supervisor

DATE 2-8-71

INV. NO. 3312-W