

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 19 1970

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 410 4th Nat. Bank Bldg. Wichita, Ks 67202

Lease Name Chitwood Unit Well No. K-9

Location C/SW/NE/NW Sec. 23 Twp. 28 Rge. 12 (E) (W)<sup>X</sup>

County Pratt Total Depth 4470

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Bert Self Casing Pulling Co.

Address Rt4 Hutchinson Ks License No. 48

Operation Completed: Hour 2:30 PM Day 16 Month 2 Year 1970

The above well was plugged as follows:

305 ft of 10 inch surface pipe cemented with 250 sacks. 4468 ft of  
5½ long string cemented with 200 sacks. Sand back to 4450 ft, 5  
sacks cement with bailer. 2000 ft of 5½ pulled. Fill hole to 275 ft,  
10 ft rock bridge, 35 sacks cement. Mud to 40 ft, 10 ft rock bridges,  
15 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Bickerton  
Well Plugging Supervisor

DATE 2/19/70  
INV. NO. 1460-W