

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address Suite 800 200 W. Douglas Wichita, Ks 67202

Lease Name Chitwood Unit Well No. L-10

Location G/E/2/NE/NW Sec. 23 Twp. 28 Rge. 12 (E) (W)

County Pratt Total Depth 4498

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks 67524 License No. 436

Operation Completed: Hour 1:00 PM Day 12 Month 3 Year 1970

The above well was plugged as follows:

314 ft of 10 3/4 surface pipe cemented with 200 sacks. 4493 ft of
5 1/2 long string with 250 sacks. Top Perf. 4395 ft. Sand back to
4380 st. 5 sacks cement with bailer. 2000 ft. of 5 1/2 pulled. Mud
to 250 ft, 10 ft rock bridge, 35 sacks cement. Mud to 40 ft, 10 ft
rock bridge, 15 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: G. Russell Bihurst
Well Plugging Supervisor

INVOICED

DATE 3/13/70

INV. NO. 1585-W