


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County, Sec. 35 Twp. 29S Rge. 8W E4W
Location as "NE/CNW1/4SW1/4" or footage from lines
660' FNL & 1980' FEL
Lease Owner Texas Oil & Gas Corp.
Lease Name Cline "B" Well No. 1
Office Address 200 W. Douglas-Suite 300, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed March 15, 1979
Application for plugging filed Verbal Application 1979
Application for plugging approved Verbal Approval 1979
Plugging commenced March 15, 1979
Plugging completed March 15, 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4,230'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,230 ft. (rotary total depth) to 270 ft. Set plug at 270 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 270 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 21st day of March, 1979

My commission expires July 25, 1982

Elsie Willison - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1979

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 35 T. 29S R. 8W
LOC. 660 FNL & 1980' FEL

FARM Cline "B" NO. 1

COUNTY Kingman

ROTARY TOTAL DEPTH 4,230'
COMM. March 5, 1979 COMP. March 15, 1979
CONTRACTOR H-30, Inc. (Rig #3)
ISSUED March 21, 1979

CASING

10 3/4"
8 5/8" Set at 286' cemented w/250 sxs cement
5 1/2"
4 1/2"

ELEVATION 1,566' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	60'
Shale and Red Bed	287'
Shale and Lime	755'
Shale	1,300'
Lime and Shale	1,551'
Shale and Lime	2,620'
Lime and Shale	3,100'
Shale and Lime	3,275'
Lime and Shale	3,904'
Shale and Lime	4,080'
Lime and Shale	4,230'
Rotary Total Depth	4,230'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 21st day of March, 1979.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

