

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

15-095-00537-0000

API NUMBER drilled 1952

LEASE NAME Cline

WELL NUMBER 1

330' Ft. from S Section Line

330' Ft. from W Section Line

SEC. 35 TWP. 29 SRGE. 8 XXX or (W)

COUNTY Kingman

Date Well Completed 02-10-57

Plugging Commenced 5-10-99

Plugging Completed 5-12-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR M T M Petroleum

ADDRESS 100 S. Main PO Box 7 Spivey, Ks. 67142

PHONE (316) 532-3794 OPERATORS LICENSE NO. 6236

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? 1957 if not, is well log attached? Well Completion Form attached

Producing Formation Mississippi Depth to Top 4142' Bottom 4189' T.O. 4290'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
See Completion	Form			10 3/4	235	
				5 1/2	4289	3040

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Sanded to 4041'. Bailed 5 sks cement. Shot at 3040'. Pulled to 1150'.

Pumped 80 barrels water and 500 pounds huls to get circulation. Pumped 35 sks cement. Pulled to 750'. Pumped 5 sks cement. Pulled to 285'. Circulated cement to surface with 170 sks. Pulled the rest of the pipe. Hole stayed full.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 249 Beth Drive Sterling, Ks. 67579-9048

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: M T M Petroleum

STATE OF Kansas COUNTY OF Kingman, ss.

Marvin A. Miller, President (Employee of Operator) or (Operator) c

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the the same are true and correct, so help me God.

RECEIVED (Signature) [Signature]
STATE CORPORATION COMMISSION (Address) P.O. Box 82 Spivey Ks 67142

KATHY HILL
Notary Public - State of Kansas
My Appl. Expires SUBSCRIBE

AUG - 6 1900 AND SWORN TO before me this 18th day of May, 19 99

CONSERVATION DIVISION
Wichita, Kansas
Kathy Hill
Notary Public

My Commission Expires: 01-04-2003

USE ONLY ONE SIDE OF EACH FORM