

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Report  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

R-8W  
NORTH

Kingman County, Sec. 29 Twp. 29S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines 150' E of C NE NW SE

Lease Owner Pan American Petroleum Corporation

Lease Name Clemmons Gas Unit Well No. 1

Office Address Box 1654, Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 2 19 61

T Application for plugging filed July 2 19 61

29 Application for plugging approved July 3 19 61

S Plugging commenced July 5 19 61

Plugging completed July 5 19 61

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred W. Hampel

Producing formation Depth to top Bottom Total Depth of Well 4305 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE      | PUT IN | PULLED OUT |
|-----------|---------|------|----|-----------|--------|------------|
|           |         |      |    | 8-5/8" OD | 260    | None       |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |
|           |         |      |    |           |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4305' to 240' Heavy mud  
1/4 sack of cottonseed hulls  
Cement to 190'  
Mud to 35'  
1/4 sack cottonseed hulls  
Cement to surface  
Well plugged

Rat Hole  
Heavy mud to 7'  
1/4 sack of cottonseed hulls  
Cement to surface

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1961

(If additional description is necessary, use BACK of this sheet)  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Herndon Drilling Company  
Address P. O. Box 489, Tulsa 1, Oklahoma

STATE OF KANSAS, COUNTY OF BARTON, ss.

F. H. Butcher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. H. Butcher Area Foreman

P. O. Box 548, Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of July, 19 61


Edna J. McPherson  
Notary Public.

My commission expires January 9, 1965

INVOICED

DATE 7/18/61

INV. NO. 3381-W





FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

| FORMATION             | TOP  | BOTTOM | FORMATION | TOP | BOTTOM |
|-----------------------|------|--------|-----------|-----|--------|
| Surface Sand and Clay | 0    | 200    |           |     |        |
| Shale and Red Rock    | 200  | 270    |           |     |        |
| Shale and Shells      | 270  | 1445   |           |     |        |
| Lime                  | 1445 | 1575   |           |     |        |
| Lime and Shale        | 1575 | 1675   |           |     |        |
| Lime                  | 1675 | 1825   |           |     |        |
| Lime and Shale        | 1825 | 2210   |           |     |        |
| Shale and Lime        | 2210 | 2500   |           |     |        |
| Lime and Shale        | 2500 | 3589   |           |     |        |
| Lime                  | 3589 | 4279   |           |     |        |
| Chat                  | 4279 | 4287   |           |     |        |
| Lime                  | 4287 | 4305   |           |     |        |
| Total Depth           | 4305 |        |           |     |        |
| Completed as Dry Hole |      |        |           |     |        |
| P & A 7-5-61          |      |        |           |     |        |