

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20,429-5000

245 North Water
Wichita, KS 67202

Operator's Full Name Imperial Oil Company

Complete Address 720 Fourth Financial Center, Wichita, Kansas

Lease Name Schieb Well No. 4-18

Location 550'ESh-550'FWk NW/4 (CN/2N/2W) Sec. 18 Twp. 31 Rge. 21 (~~East~~) (West)

County Clark Total Depth 5263'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Eagle Drilling Co. and Sun Oil Well Cementing

Address 210 Rockborough Bldg, 260 N. Rock Road, Wichita, KS License No. _____

Operation Completed: Hour: 10:30 PM Day: 13 Month: December Year: 1980

The above well was plugged as follows: 8 5/8" - 645' - 175 sacks Common 200 sacks light cement.

Hole filled with mud. 55 sacks cement pumped through drill pipe at 655'. 25 sacks cement pumped through drill pipe at 200'. Plug and 1/2 sack bulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.

Rathole cemented with 5 sacks cement.

Mousehole cemented with 5 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1980

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-20-81

INV. NO. 3961-W

Signed: [Signature]
Conservation Division Agent
CONSERVATION DIVISION
Wichita, Kansas