

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20580-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Mesa Petroleum Co.

Complete Address Box 2009, One Mesa Square Amarillo Texas 79105

Lease Name Moore Well No. 5-20

Location 750' FSL - 1490' FWL Sec. 20 Twp. 31 Rge. 2 (East)(West)

County Clark Total Depth 5351'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling Co. Inc.

Address 210 Rockblorough Bldg 2601 N Rock Rd. Wichita, Kansas 67206 License No. _____

Operation Completed: Hour: 6:30 AM Day: 14 Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

1st plug was at 1080' with 60 lbs of cement. 2nd plug at 720' with 40 lbs of cement. 3rd plug was at 40' to 0' on solid bridge with 10 lbs of cement. Then they circulated 10 lbs of cement in rat hole & 5 lbs of cement in mouse hole. They pumped the cement through drill pipe with hole full of heavy mud. They had topped the anhydrite at 1020'. The plugging was accomplished by Dowell Cementing

Amount of Surface Casing: 679' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttig
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I couldn't be at two pluggings at the same time but made it to this well as soon as I could

Signed: Paul A. Luttig
Conservation Division Agent

INVOICED RECEIVED
STATE CORPORATION COMMISSION
DATE 5-28-82
MAY 18 1982
5-18-82
CONSERVATION DIVISION
Wichita, Kansas

173.91