

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20,469-6000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Moly Oil Co

Complete Address R.P. #2 Box 54 Kiowa Kansas 67070

Lease Name Carol Well No. 1

Location NW-SE Sec. 30 Twp. 31 Rge. 21 (East)(West)

County Clay Total Depth 5191'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was equipped & tested but not produced

Plugging Contractor Vertical Casing Pulling Inc.

Address P.O. Box 347 Pond Creek Okla 73766 License No. 979

Operation Completed: Hour: 2:00 PM Day: 24 Month: March Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They set 4 1/2" of 5180' of production pipe. The perforations were from 5115' to 36'. 1st plug cast iron plug set at 4650' with 20' of cement on top of it. 2nd plug at 750' with 50 sby of cement. 3rd plug at 40' to 0' with 15 sby of cement. They recovered 3328' of 4 1/2" production pipe. The plugging was accomplished by Vertical Casing Pulling Inc. They had the hole full of heavy mud & pumped the plugs down through production pipe.

Amount of Surface Casing: 711' of 8 1/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1982

Signed: _____
Conservation Division Agent

INVOICED

DATE 3-30-82

INV. NO. 9820-W