

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

12-20-65
DEC 20 1965

Operator's Full Name Sunray DX Oil Company 15-004-30197-0600

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name Ernest McGuire Well No. # 1

Location C NE NW Sec. 22 Twp. 31 Rge. 13 (E) (W) W.

County Barber Total Depth 3810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 5:30 AM Day 19th Month Dec. Year 1965

The Above well was plugged as follows:

288' of 13 3/8" surface pipe, cement circulated with 300 sacks. Hole
was filled with drilling mud to 275', 1st cementing plug, bridged solid
with hulls on fluid at 275', and cemented with 50 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls on fluid at 40', and cemented with 30
sacks to the base of the cellar. Rat and mouse holes bridged and cement-
ed with 5 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/20/65
INV. NO. 2441-W