

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 13 1962

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dec. 8, 1962.

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Jack Cowden of Continental Oil Co. has this

date requested permission to plug the following described well:

Mr. Jack Cowden guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 30, Lyons, Kansas.

Lease Name: Louise K. Martin #1 Well No. #1

Location: SW-SW-NE Sec. 20 Twp. 28S Rge. 12 (E) (W) X

County Pratt County Total Depth 4546' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jack Cowden was instructed to plug the well as follows:

912' of 10 3/4" surface pipe circulated with 458 sacks
cement. Hole filled to 200' with heavy drill mud, 1/4 sack
hulls, 1st cementing plug & 25 sacks cement. Hole filled to
40' with heavy drill mud, 1/4 sack hulls, 2nd cementing plug
and 15 sacks cement to base of cellar, rat hole bridged and
2 sacks cement.

Very truly yours,

Herman J. Gustus
 Conservation Division Agent