

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-129-10003-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of D.J. Stone has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: D.J. Stone

Complete Address: 217 Town & Country village, Palo Alto, California, 94301

Lease Name: Henke Well No. 1

Location: SW SE Sec. 32 Twp. 31 Rge. 41 (W)

County Morton Total Depth 5344' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1504' circulated w/ cement. 5 1/2" to 5344' cemented.

Top perforations 5242' Plug bottom w/ 20 sacks cement.

Top of cement 5050' Mud 5050' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent