



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-129-20201-0000

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Earl F. Wakefield of Earl F. Wakefield, Inc. has this date requested permission to plug the following described well:

Mr. Wakefield guarantees payment of the plugging fee.

Operator's full Name: Roger M. Wheeler

Complete Address: P. O. Box 1526, Tulsa, Oklahoma 74101

Lease Name: KANSAS UNIVERSITY ENDOWMENT Well No. 1

Location: C SE NE Sec. 32 Twp. 31S Rge. (E)(W) 41W

County: Morton Total Depth 5367' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Wakefield was instructed to plug the well as follows:

8-5/8" surface pipe set at 1490'.  
Cement 2700' to 2600' with 25 sxs cement. Cement 2400' to 2300' with  
25 sxs. cement. Cement 2100' to 1900' with 25 sxs cement. Cement  
1500' to 1440' with 30 sxs. cement. Cement 40' to 0' with 15 sxs  
and 15 sxs in rat hole.

Very truly yours,

  
Conservation Division Agent