



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Stevens of Rains & Williamson Drlg Co. has this

date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co. & Don D. Sharver

Complete Address: 1425 Wichita Plaza Wichita, Ks

Lease Name: Sparr Well No. 1

Location: S $\frac{1}{2}$ S $\frac{1}{2}$ NW1/4 Sec. 32 Twp. 30s Rge. 5 (E)(W) W

County: Kingman Total Depth 4575 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

254 ft of 8 5/8 surface pipe cemented with 225 sacks. Fill

hole to 250 ft, plug, $\frac{1}{2}$ sack hulls, 25 sacks cement. Mud

to 40 ft, plug, $\frac{1}{2}$ sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,


Conservation Division Agent