



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

13 May 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-025-20580-1000

Dear Sir:

Mr. Butch Steinert of Eagle Drilling Co. Inc., has this date requested permission to plug the following described well:

Operator's Full Name: Mesa Petroleum Co.

Complete Address: Box 2009, One Mesa Square, Amarillo Texas 79105

Lease Name: Moore Well No. 5-20

Location: 750' FSL-1490' FWL Sec. 20 Twp. 31 Rge. 21 (E) (W)

County: Clark Total Depth: 5351

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Steinert was instructed to plug the well as follows:

They cement circulated 679' of 8 5/8" surface casing. 1st plug at 1080' with 60 skyp of cement. 2nd plug at 720' with 40 skyp of cement. 3rd plug on solid bridge at 40 to 50' with 10 skyp of cement. Then they circulated the rat hole with 10 skyp of cement. 5 skyp of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Dowell Cementing.

Very truly yours,
RECEIVED
STATE CORPORATION COMMISSION
Paul A. Lattin
Conservation Division Agent
MAY 18 1982
5-18-82
CONSERVATION DIVISION
Wichita, Kansas