

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-095-00704-0000
12-7-50 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. # 5003 6-92

ADDRESS 110 South Main Suite 500 Wichita, Ks 67202 PHONE # (316) 265-9697

LEASE (FARM) Bolinger "A" WELL NO. #1 WELL LOCATION SW SW NE COUNTY Kingman

SEC. 21 TWP. 28S RGE. 5W (Ⓢ) or (Ⓜ) TOTAL DEPTH 3836' PLUG BACK TD _____

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 207' CEMENTED WITH 125 SACKS

CASING SIZE 5-1/2" SET AT 3807' CEMENTED WITH 150 SACKS

PERFORATED AT Open Hole 3807-3836' TOC @ 3020'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Set CIBP @ 3750' & cap with 2 sacks of cement. Stretch
& shoot 5-1/2" casing. Pull casing to 700' & spot 30 sacks of cement. Pull casing
to 300' & circulate cement to surface. Pull remaining 300' of casing & top off cement.
60/40 Poz 4% Gel (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 11, 1992

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 532-5292

ADDRESS Kingman, KS

PLUGGING CONTRACTOR Shawnee Well service LICENSE NO. 30346

ADDRESS P. O. Box 781624, Wichita, KS 67278 PHONE # (316) 254-7893

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Roy McCoy
(Operator or Agent)

DATE: 5-8-92

2

RECEIVED
MAY 11 1992
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

15-095-00704-0000

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 11, 1992

McCoy Petroleum Corp
110 S Main 500
Wichita KS 67202

Bolinger A 1
SW SW NE
Sec. 21-28-05W
Kingman County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #2 202 W First Suite 304
Wichita KS 67202
(316) 263-8809