

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-095-00704-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. # 5003

ADDRESS 110 South Main Suite 500 Wichita, Ks 67202 PHONE # (316) 265-9697

LEASE (FARM) Bolinger "A" WELL NO. #1 WELL LOCATION SW SW NE COUNTY Kingman

SEC. 21 TWP. 28S RGE. 5W ~~(E)~~ or (W) TOTAL DEPTH 3836' PLUG BACK TD         

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO.         

SURFACE CASING SIZE 8-5/8" SET AT 207' CEMENTED WITH 125 SACKS

CASING SIZE 5-1/2" SET AT 3807' CEMENTED WITH 150 SACKS

PERFORATED AT Open Hole 3807-3836' TOC @ 3020'

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 3750' & cap with 2 sacks of cement. Stretch

& shoot 5-1/2" casing. Pull casing to 700' & spot 30 sacks of cement. Pull casing

to 300' & circulate cement to surface. Pull remaining 300' of casing & top off cement.

60/40 Poz 4% Gel (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?   
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN May 14, 1992

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson

PHONE # (316) 532-5292

ADDRESS Kingman, KS

PLUGGING CONTRACTOR Shawnee Well Service

LICENSE NO. 30346

ADDRESS P. O. Box 781624, Wichita, KS

PHONE # (316) 254-7898

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

[Signature]  
(Operator or Agent)

DATE:

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 08 11 1992  
CONSERVATION DIVISION  
Wichita, Kansas