

RECEIVED

SEP 04 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/82)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-095-21831-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419
(owner/company name) (operator's)

ADDRESS P.O. Box 438 CITY Haysville

STATE Kansas ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE Dalton WELL# 1 SEC. 17 T. 28 R. 5 (East/West)

NE NE NE SPOT LOCATION/0000 COUNTY Kingman

4950 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 229 CEMENTED WITH 235 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3889 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Mississippi Chert 3746'-56' 10'

ELEVATION 1385 T.D. 3890 PBD 3760 ANHYDRITE DEPTH ?
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 3695', dump bail 4 sax cement, shoot pipe off, put to 850' FS, spot 35 sax, pull to 450' FS, spot 35 sax, pull to 280' FS, circulate cement to surface, pull remaining pipe, top hole off 60/40 poz 4% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no

If not explain why? Will send in with CP-4

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Schremmer PHONE# (316) 524-1225

ADDRESS P.O. Box 438 City/State Haysville, KS 67060

PLUGGING CONTRACTOR Gressel Oil Field Service, Inc. KCC LICENSE # 3009 3004
(company name) (contractor's)

ADDRESS P.O. Box 607, Burrton, KS 67020 PHONE # (620) 463-5161

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) unknown 8-13-03

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4-16-03 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)



FIELD ORDER N^o 24065

BOX 438 • HAYSVILLE, KANSAS 67060
316-524-1225

DATE 8-3-07 2007

IS AUTHORIZED BY: Bear Petroleum Inc.
(NAME OF CUSTOMER)
Address Box 438 City Haysville State Ks
To Treat Well As Follows: Lease Deltin Well No. 4 Customer Order No. _____
Sec. Twp. Range _____ County Kingman State Ks

CONDITIONS: As a part of the consideration hereof it is agreed that Copeland Acid Service is to service or treat at owners risk, the hereinbefore mentioned well and is not to be held liable for any damage that may accrue in connection with said service or treatment. Copeland Acid Service has made no representation, expressed or implied, and no representations have been relied on, as to what may be the results or effect of the servicing or treating said well. The consideration of said service or treatment is payable. There will be no discount allowed subsequent to such date. 6% interest will be charged after 60 days. Total charges are subject to correction by our invoicing department in accordance with latest published price schedules.

The undersigned represents himself to be duly authorized to sign this order for well owner or operator.

THIS ORDER MUST BE SIGNED BEFORE WORK IS COMMENCED

Well Owner or Operator

By

Dick

Agent

CODE	QUANTITY	DESCRIPTION	UNIT COST	AMOUNT
<u>4100</u>	<u>1</u>	<u>Pump truck for plug job</u>		<u>400-</u>
<u>4101</u>	<u>45</u>	<u>Pump truck mileage</u>	<u>2.00</u>	<u>90-</u>
<u>4000</u>	<u>350</u>	<u>sax 60/40 puz 42 gel</u>	<u>5.85</u>	<u>2047.50</u>
<u>4200</u>	<u>350</u>	<u>Bulk Charge</u>	<u>1.00</u>	<u>350-</u>
<u>4201</u>	<u>45</u>	<u>Bulk Truck Miles 15.4 ton</u>	<u>1.85</u>	<u>829.25</u>
		Process License Fee on _____ Gallons		
		TOTAL BILLING		<u>3,476.55</u>

I certify that the above material has been accepted and used; that the above service was performed in a good and workmanlike manner under the direction, supervision and control of the owner, operator or his agent, whose signature appears below.

Copeland Representative Dean + Joe

Station _____

Well Owner, Operator or Agent

Remarks _____

NET 30 DAYS

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

Date	Invoice #
8/22/2003	9637

Bill To
Bear Petroleum, Inc. P.O. Box 438 Haysville, Kansas 67060

RECEIVED
SEP 04 2003
KCC WICHITA

P.O. No.	Lease	County
	Dalton #1	Kingman

Qty	Description	Rate	Amount
20	Hours Rig Time	130.00	2,600.00T
1	Shot	150.00	150.00T
	Charge To Move Floor	100.00	100.00T
4	Sacks Cement	10.50	42.00T
	Sand	20.00	20.00T
	8-11-03 Set in on location, rigged up, checked the hole, picked up sand and cement, backhoe dug cellar and pit, sanded off bottom to 3620', loaded the hole, had to move tubing to set in floor. 6 Hours.		
	8-12-03 Drove to location, checked sand, dumped 4 sacks cement on top, rigged up floor, pulled slips and got stretch. 4 Hours Operator sick.		
	8-13-03 Drove to location, shot casing @3020', pipe parted @1970', pulled up to 850', broke circulation, pumped 35 sacks cement, pulled up to 450', pumped 35 sacks cement, pulled up to 280' and circulated cement to surface. Layed down rest of pipe, tore down and moved off. Plugging Complete.		
	Sales Tax	5.30%	154.34
		Total	\$3,066.34